

Age Concern Epsom & Ewell 'In Memory Woodland' Planting list

Existing Scots Pine cluster

To be enhanced with additional Scots pine or similar. Proposed positions shown on plan.
To supply 7no. 90-120cm root balled Pinus sylvestris. Tree stakes and irrigation tube included.
Strimmer guards included.

Boundary tree planting in line with green metal fence

To supply 6no. 1.5 Ulmus laevis feathered maidens, potted.
Planted on the side of the island bed (1) as per plan.

Island bed (1).

To supply underplanting of Viburnum opulus, Spindle, Alder Buckthorn, Ruscus. (10no. Potted shrubs and 10 whips.
Under planting to not compete with the trees.
Tree stakes and irrigation tube included.
Plant woodland bulbs: Daffodils, Wood Anemones, Bluebells.

Circular island beds (2,3, 4).

Each bed planted with a mix of ornamental Hawthorns, Rowan, Small fruit Malus, Small flowering cherries. Stem size up to 10-12 cm circumference. Tree stakes and irrigation tube included.

Bed 2 5 trees Tree stakes and irrigation tube included.
Bed 3 7 trees Tree stakes and irrigation tube included.
Bed 4 7 trees Tree stakes and irrigation tube included.
Plant woodland bulbs in each bed: Daffodils, Wood Anemones, Bluebells.

Community bed (5)

This bed to be planted with small tree whips from the TAB nursery and similar tree mix to island bed 1.
5no. 10-12 saplings included. Native trees. (Not Oak).
This bed to provide a range of smaller young trees.

Elm corner.

To plant a group of 3no. Disease resistant elms, Ulmus Ademuz in corner in a dedicated island bed. Feathered sapling.
Underplant with Butchers Broom. Metal tree guards and stakes included. Tree stakes and irrigation tube included.
Plant woodland bulbs: Daffodils, Wood Anemones, Bluebells.

Birch group.

To plant 5 no. single stem and multi-stem Chinese Silver birch. Stem size 10-12 cm circumference.
Tree stakes and irrigation tube included. Strimmer guards included.

Service tree (Sorbus torminalis)

To add additional two Service trees with the solitary Service tree near gate. Stem size 12-14cm circumference. Tree stakes and irrigation tube included. Strimmer guards included.

Centre tree for visual impact. Not Cedar tree.

To install evergreen conifer. Abies Concolor Swifts Silver. Tree stakes and irrigation tube included.

All beds and trees to be mulched.

Sundries

Support posts, planting fertiliser, irrigation pipe, Hessian ties, weedkiller to prepare areas, digger to prepare beds, soil conditioner, deliveries, bulbs, other under-planting, bark mulch all planted areas.

September 2023